

Facility Development in Today's Climate "Post-Covid"

And Architecture's Role in the Solution

"To create, one must question everything."



Facility Development in Today's Climate – "Post-Covid"


And Architecture's Role in the Solution

Presenter:

Paul Mussman

President, Mussman Architects





Current Challenges with Facility Development

- Land Acquisition/Due Diligence
- Design Schedule/Permitting Delays
- Construction Costs/Material Delays
- Borrowing Costs/Bond Rates
- Labor Market

Strategies to Mitigate challenges in the Development Process

- Cost Control
- Schedule Control
- Teamwork | Delivery Model
- Good Design



Big Picture Overview

Average Charter School Project	2+ years ago	Today
Land Costs	X	+15%
Land Due Diligence (ex. Surveys)	30 - 45 days	60(+) days
Design Timelines	3 - 4 months	3 – 5(+) months
Permitting Timelines	45 days	60 - 90 days
Construction Costs	Χ	+25%
Construction Timelines	10 months	10 - 14 months
Borrowing Costs / Bond Rates	4%	5% +
Labor Costs	X	Increasing Costs





Construction Costs Overview

Construction Costs	2+ years ago	Today	Trending
Lumber	X	+85%	\
Concrete	X	+12%	
Steel	X	+120%	\
Electrical Gear	X	+50%	
Mechanical/HVAC Equipment	X	+100%	
Roofing	X	+75%	
Gypsum Board	X	+40%	







Schedule Challenges


Average Charter School Project Development	Avg Timeline	
Land Acquisition Timelines	Varies (6 months)	
Find and Evaluate Potential Properties		
Negotiate Offer		
Perform Due Diligence		
Rezoning? Special Exception?	_	
Close		
Design & Permitting Timelines	6 - 9 months	
Site Planning & Design		
Building Design		
Site Permitting	A	
Building Permitting		
Construction Timelines	10 - 14 months	
Pricing Phase		
Construction Phase	.ļ ↑	

Total Project Development


Today (average) 25 months 2+ years ago 20 months



Project 'X' Example













<u>Understanding the Market</u>

What do we NOT control?

- PERMITTING TIMELINES
- MATERIAL LEAD TIMES
- CONSTRUCTION & MATERIAL COSTS
- INTEREST RATES
- While we do not control these, the facility team MUST react to each of these and plan/design your project accordingly





<u>Understanding the Market</u>

What DO we control?

PLANNING | DESIGN

- 1. Collaborative design process has become increasingly important to deliver projects
 - Your facility team should be a highly collaborative group consisting of:
 - Finance Team
 - Contractor / Design-Builder
 - Architects
 - Engineers
 - Careful planning, design, and execution will improve quality and control costs
- 2. Re-evaluate everything about the planning, design, construction process
 - Everything should be on the table (each project is unique)
 - Obvious things like Structural Systems (Wood, Steel, Concrete)
 - No-so-obvious things like the SIZE of your facility (good design)
 - Prototype Design?
 - Flexibility in the design solution (facility team needs to react quickly to market)

BUDGET | SCHEDULE

- Set a realistic budget and schedule and continuously track through all phases
- Solicit multiple bids on each trade and negotiate each bid
- Order materials early to minimize delays and cost impacts



How do we react to rising costs and instability with materials?

Evaluate all available materials for cost and lead times. The team will need to decide which materials are optimal for a given project. Be willing to use innovative strategies

Pre-Engineered Metal Building



Steel Frame




Wood Frame




Concrete















CASE STUDY: MANAGING COSTS & SCHEDULE

The Gathering Place
Charter School





The Gathering Place Charter School

- Began design in May 2020 (during the Covid shutdown)
- 2. 27,000 sqft to house 400 students (*only 68 sqft per student)
- 3. Construction Costs were rising
- 4. Material shortages had surfaced
- 5. Permitting took place virtually (all permit officials working from home)
- 6. Construction started in October 2020
- 7. Construction was completed on time in August 2021 (Contractual time was 15 months however +/- 4 months of work was performed prior to contracts
- 8. Total Cost 5.8 million = 214/sft






- Contractor and Architect worked very close together during the planning and design phase. Construction Manager at Risk delivery model
- 2. Hybrid structural system utilized available materials and utilized lowest cost materials
- 3. School wanted the natural wood look on the exterior. The design minimized the wood materials (expensive) but didn't eliminate them
- Materials ordered early and stored to beat price increases. Design process itself had to be designed and organized to produce finalized material selections early.
- Design team worked closely with school to design an efficient floor plan with high utilization rate which minimized square footage











Good Design = Better Results!

How can good design mitigate rising construction costs?

- 1. Understand the utilization rate of your space. Designing for highutilization and multi-fuctional spaces reduces your square footage
- 2. Activate your corridors. Make them commons spaces.
- 3. Masterplan your facility so you can take advantage of phasing and reduce re-work when it is time to expand
- 4. Minimize footprint to minimize site costs
- 5. Use 'cheap' materials in ways that make them look high-end. This requires a creative designer with experience in these types of facilities
- 6. Don't be afraid to use nice materials, just use them effectively (not en mass).

How does good design reflect post – covid teaching pedagogies?

- 1. More physical teaching space outdoors. Use covered spaces with fans/heaters.
- 2. Touchless restrooms
- 3. Natural Ventilation / Bi-polar ionization incorporated into the HVAC strategy
- 4. Windows and Overhead doors bring natural light indoors and help with making connections to outdoor learning spaces













The New Normal

1 Project Team

All team members must be engaged early and coordinating throughout the project

Entire team, including the school, must develop a mutual trust because there will be many obstacles and setbacks

2 Material Selections

Understanding a rapidly changing market (what is available?)

Essential to consider hybrid systems of materials

Collaboration between Contractor, Architect and Engineers essential

3 Budget

Minimize expensive materials, don't necessarily eliminate them

Order materials early to avoid price increases

Maximize the utilization rate of your facility

4 Schedule

Reacting quickly to everything happening slower – lead times, permit timelines

Front loading the schedule – requires more work upfront

School must be prepared to make more decisions earlier

"To create, one must question everything."



Summary

Contact Info

Paul Mussman 864-626-6330 paulm@mussmanarchitects.com



1. Start design process early! - Good design takes time!

What is early??

18-24 months for the average facility project design and construction (This does not include site acquisition, due diligence, etc)

Make sure you have a team of design and construction professionals actively working on your project

Remember that every project is different and will face different challenges

2. Identify the project challenges

Stay on top of each hurdle - communicate!

3. Re-evaluate the development process

Don't be afraid to innovate! Be flexible with your design solution